



MINI-CAISSON NOTES:

1. ALL MINI-CAISSONS (DENOTED AS) SHALL BE INSTALLED AT LOCATIONS SHOWN IN CONTRACT DRAWINGS.
2. ALL MINI CAISSON MATERIALS AND OPERATIONS SHALL BE IN COMPLIANCE WITH THE REQUIREMENTS OF THE NEW YORK CITY BUILDING CODE.
3. MINI CAISSON CAPACITY, DRILLING PROCEDURE, CASING SIZE, MATERIAL, GROUT STRENGTH AND REINFORCING SHALL BE SUBMITTED TO THE OWNER'S GEOTECHNICAL ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ANY CAISSON WORK.
4. DRILLED MINI CAISSONS SHALL BE INSTALLED PER GEOTECHNICAL ENGINEER'S APPROVAL AND SHALL HAVE A MINIMUM ALLOWABLE CAPACITY OF 120 TONS.
5. ALL MINI CAISSONS SHALL BE SOCKETED INTO BEDROCK TO A DEPTH APPROVED BY THE GEOTECHNICAL ENGINEER.
6. SEE GENERAL NOTES AND GEOTECHNICAL REPORT FOR ADDITIONAL REQUIREMENTS.

8 7/20/07 Revision 6
 7 5/17/07 Revision 5
 6 3/23/07 Revision 4
 5 2/23/07 Revision 3
 4 1/26/07 Revision 1
 3 10/13/06 Issued for Construction
 2 06/01/06 Issued for BID
 1 12/21/05 Issued for DOB
 no. date revision

HAGE ENGINEERING PC
 STRUCTURAL CONSULTANTS
 65 Bleecker Street, 11th Floor
 New York, New York 10012
 tel: 212.358.7778
 fax: 212.358.7772

project:

THE DEUCE
 534 W42ND ST.
 NEW YORK, NY

drawing title:

FOUNDATION & CELLAR PLAN
 & FIRST FLOOR PLAN

job #: 1681

drawn by: ABC/WD

checked by: MH

issue date: 12/21/05

scale: 1/4" = 1'-0"

drawing #:

S-1